

Suklaphata Municipality
Office of Municipal Executive
Jhalakothi Bhanpur
 Sudurpashchim Province, Nepal

BILL OF QUANTITY

[Handwritten Signature]

मन्त्रालयको कार्यालय

Name Of Project:- Maintanance work of old resource /training hall at Krishna mavi
 Location :-Shu.na.pa ward no 10

F/Y:- 2082/83

SN	Description of Items	Quantity	Unit	Rate		Total Amount	Remarks
				Bidder's rate(In Digit)	Bidder's rate(In words)		
A	Civil works						
1	Excavation in foundations in all type of soils for foundation, trenches, footing, pits etc. to the required depth including dewatering by manual or mechanical means etc. as per specifications with all contractor's own machinery and equipment's, providing crossing of track, shoring, strutting, timbering and buttressing with appropriate materials and all such measures necessary to retain in position the sides of the foundation pit and including refilling the excavated material with watering, ramming, leveling the site and disposing off the surplus/unusable earth to outside the construction premises, etc. all complete as per drawings, specifications and instructions of the Engineer.	0.45	Cu.m				
2	Providing and Laying Stone Soling in foundation and floor of approved size and quality to level and line and compaction using appropriate mechanical means with all contractors materials, handling, placing, etc. along with filling the gaps with suitable quarry waste or quarry sand all complete work as per site instruction of Engineer.	0.45	Cu.m				



Handwritten signature and stamp of the Engineer in Charge, with the text 'ಇಂಜಿನಿಯರ್ ಅಧಿಕಾರಿ' (Engineer in Charge) written vertically.

3	Providing and laying machine mixed Plain Cement Concrete of nominal mix 1:3:6 (1 cement : 3 sand : 6 coarse aggregate) for leveling course in foundations and under floor of building, etc. in all level with broken stone aggregate of size not more than 25 mm of approved quality including formwork wherever necessary, dewatering, batching, mixing, transporting, placing, compacting, curing, including all lead and lift, etc. all complete as per drawings, specifications and the instructions of the Engineer.	0.89	Cu.m			
4	Providing & laying 1st class local chimney made brickwork in 1:6 C/S mortar in substructure, Ground floor and above floors in perfect line level finish including the cost of single or multi stage scaffolding, wetting the bricks, racking the joints, provision for recesses, openings, toothing and curing the work for at least 7 days as per specification, drawings & instructions of the site engineer.	0.42	Cu.m			
5	Providing and applying at all levels and shape 12.5 mm thick cement plaster in building walls, ceiling, floors, etc. in specified cement mortar with 1:4 (1 cement :4 fine sand) in all surface at all height including mixing mortar, laying in perfect line, level and plumb and finishing in regular and even surface including all necessary single or multi-stage scaffolding, making grooves and recesses, throating, dusting, dripping, wetting, curing, protection, etc., all complete as per drawing , specification and instruction of the Engineer.	3.65	Sqm			
6	Providing and applying two or more coats of first quality plastic emulsion paints from Asian paints or Berger paints or KNP of approved shade and pattern to the interior walls and ceilings of buildings etc., The rates shall include for scrapping , washing the surface with water, applying a coat of approved quality water base cement primer, surface preparation, scaffolding etc., all complete as per the manufacturer's recommendations and as approved by the Engineer.	178.88	Sqm			
7	Double coat Water proof cement paint (Snowcem) application in wall	152.41	Sqm			
8	Supplying and painting One coat of ready made enamel paint of approved quality and colour with one coat of primer from Asian paints or Berger paints or KNP painting porperly cleaned surface all complete.	20.20	Sqm			



गणतन्त्र नेपाल
नगर कार्यपालिकाको कार्यालय
प्रहारा, काभ्रेपलाञ्चन
सुदूरपश्चिम प्रदेश, नेपाल

OK ✓

प्रमुख प्रशासक अधिकृत

9	26 gauge G.I Mosquito proof net/mesh for window	16.50	Sqm				
10	Saal Wood listi for mosquito netting of window	103.20	rm				
11	38mm thick (1:2:4) P.C.C.(DPC) for flooring with punning, rubbing in hard surface curing.	51.31	rm				
B Electrical work							
12	Surface Wiring using standard Pvc Pipe and 3/20 , 3/22 and 3/18 or equivalent wires for Points supply and installation as per need and specification and instructed by site incharge .	14.00	Pt				
13	Surface Wiring using standard pvc Pipe and 3/20 , 3/22 and 3/18 or equivalent wires for power socket (15 Amphere) supply and installation as per need and specification and instructed by site incharge .	3.00	Pt				
14	6TPN Double cover Main distribution board	1.00	No.s				
15	ISI /NS 48" ceiling fan	6.00	No.s				
16	15 watt CFL bulb supply and installation as per need and specification and instructed by site incharge .	8.00	No.s				
C Truss roof							
17	Colourfull 26 SWG (.37mm thick Standard wire gauge) C.G.I. sheet roofing works with supply of materials all complete	139.03	sqm				
18	Making ridge(2 ft.) of 26 gauge C.G.I. plain sheet and fitting with supply of materials all complete	13.42	rm				
19	Miscelleous work like existing truss postpaint,removing existing cgi sheet,removing of old damage plaster ,removing of existing floor section,fitting and fixing of board,etc as per supervision	1.00	ps				
20	Iron railing Work with one coat enamel	17.33	kg				
21	12.5mm thick Gypsum Board False ceiling with GI Channel 0.4mm*0.26mm*0.26mm and 0.26mm thick hanger- Norman Gypsum Board	66.42	sqm				



ಕರ್ನಾಟಕ ಸರ್ಕಾರ
ಬೆಂಗಳೂರು, ಕರ್ನಾಟಕ
ಪುನರ್ಮಿಷನ್ ಪ್ರಾ. ಸಂಸ್ಥೆ

(Handwritten signature)

ಪುನರ್ಮಿಷನ್ ಪ್ರಾ. ಸಂಸ್ಥೆ

D	Meeting hall projectionable Board					
22	Sal board Frame for support of board	0.03	cu.m			
23	19 mm water Plywood for board	4.81	sqm			
24	Formaica for Board	4.59	sqm			
					Sub-total Amount	
					Vat @ 13 %	
					Contingency @ 2%	
					Total Amount	

In words:

Name of Firm:

Address of Firm:

Athorized Signature and Date :

Office Seal: