


Shuklaphanta Municipality  
Office of Municipal Executive  
Jhalari, Kanchanpur  
Sudurpashchim Province, Nepal

**BILL OF QUANTITY**

Name of Project:- Truss for bike stand  
Location:- Shuklaphanta Ward No-10, Jhalari Kanchanpur  
Municipality:- Shuklaphanta Municipality

F/Y:2082/83

SN	Description of Items	Quantity	Unit	Rate		Total Amount	Remarks
				Bidder's rate(In Digit)	Bidder's rate(In words)		
A	<b>Civil works</b>						
1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means , In area of light jungle (less than 15 number per 100 sqm )	196.00	Sqm				
2	Excavation in soft clay and silty soil having lead upto 10m & lift upto 1.5m as per Drawing and Technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instrution of the Engineer	1.84	Cum				
3	Earth work Filling in with Ordinary soil, spreading in layers of 15/15 cm, spraying water & Manual Compaction including lead upto 10 m as per Drawing and instrution of the Engineer	0.37	Cum				



Shuklaphanta Municipality  
Office of Municipal Executive  
Jhalari, Kanchanpur  
Sudurpashchim Province, Nepal

**BILL OF QUANTITY**

Name of Project - Truss for bike stand  
Location - Shuklaphanta Ward No-10, Jhalari Kanchanpur  
Municipality - Shuklaphanta Municipality

FY 2082/83

SN	Description of Items	Quantity	Unit	Rate		Total Amount	Remarks
				Bidder's rate (in Digit)	Bidder's rate (in words)		
4	Gravel in Filling: Earth work in filling in foundation, floor etc. with ramming	26.85	Cum				
5	Stone filling work in foundation trench & Levelling including 30 m lead/Used alternatively as soiling	0.43	Cum				
6	P.C.C. work 1:2:6 in Foundation, Wall including 30 m lead using machine	0.14	Cum				
7	P.C.C. work 1:2:4 in Foundation, Wall including 30 m lead using machine	3.19	Cum				
8	Ms Truss : Making & fixing of black pipe tubular truss with one coat primer paint as per instruction of site engineer.	1558.71	kg				

प्रमुख प्रशासकीय अधिकृत

Shuklaphata Municipality  
Office of Municipal Executive  
Jhalari, Kanchanpur  
Sudurpachini Province, Nepal

BILL OF QUANTITY

Name of Project:- Truss for bike stand  
Location:- Shuklaphanta Ward No-10, Jhalari Kanchanpur  
Municipality:- Shuklaphanta Municipality

FY:2082/83

SN	Description of Items	Quantity	Unit	Rate		Total Amount	Remarks
				Bidder's rate(In Digit)	Bidder's rate(In words)		
9	Colourfull 26 SWG (.37mm thick Standard wire gauge) C.G.I. sheet roofing works with supply of materials all complete	205.50	Sqm				
10	Making ridge(2 ft.) of 26 gauge C.G.I. plain sheet and fitting with supply of materials all complete	27.95	rm				
						Sub-total Amount	
						Vat @ 13 %	
						Contingency @ 2%	
						Total Amount	

In words:  
Name of Firm:  
Address of Firm:  
Athorized Signature and Date :  
Office Seal: