

Shuklaphata Municipality
Office of Municipal Executive

Jhalari, Kanchanpur
Sudurpachim Province, Nepal

शुक्लाफाँटा नगरपालिका
झालारी, कञ्चनपुर
सुदूरपश्चिम प्रदेश, नेपाल

BILL OF QUANTITY

प्रास्ताविक अर्पण

Name of Project:- वडाको विभिन्न ठाउँमा तटबन्ध, जैविक तटबन्ध तथा निर्माण कार्य
Location:- Ward No-02

Municipality:- Shuklaphanta Municipality

FY:2082/83

SN	Description of Items	Quantity	Unit	Rate		Total Amount	Remarks
				Bidder's rate(In Digit)	Bidder's rate(In words)		
A	Civil works						
1	Earth work excavation in foundation, trenches in soft and medium soil including lift upto 1.5 m and disposal upto 10 m away from site as per need and specification all complete work.	33.93	Cum				
2	Mud Filling as per instruction	54.27	cum				
3	Earthwork Backfilling work @ 20% of E/W excavation	3.74	cum				
4	Supplying of Heavy Zinc Coating machine made gabion box of wire mesh Dia 3.00mm having 100mm*120mm double twist hexagonal mesh size selvedge wire Dia 3.9mm and Lacing Wire Dia 2.4mm. (2X1X1/1)	47.00	Nos				
5	Supplying of Heavy Zinc Coating machine made gabion box of wire mesh Dia 3.00mm having 100mm*120mm double twist hexagonal mesh size selvedge wire Dia 3.9mm and Lacing Wire Dia 2.4mm. (3X1X1/2)	4.00	Nos				
6	Providing and filling stone/boulder in gabion boxes/mattress etc.. Including dressing, bedding, bonding all complete as per Drawing and Technical Specifications.	106.00	Cum				

Shuklaphanta Municipality
Office of Municipal Executive

Jhalari, Kanchanpur
Sudurpachhim Province, Nepal



BILL OF QUANTITY

मुख्य प्रशासकीय अधिकारी

Name of Project:- वडाको विभिन्न ठाउँमा तटबन्ध, जैविक तटबन्ध तथा निर्माण कार्य
Location:- Ward No-02

Municipality:- Shuklaphanta Municipality

F/Y:2082/83

SN	Description of Items	Quantity	Unit	Rate		Total Amount	Remarks
				Bidder's rate(In Digit)	Bidder's rate(In words)		
7	Laying and fixing of Geo-Textile all complete as per specification.	68.09	Sqm				
8	Stone filling work in foundation trench & Levelling including 30 m lead/Used alternatively as soling	0.90	Cum				
9	P.C.C. work 1:3:6 in Foundation,Wall including 30 m lead using machine	0.30	Cum				
10	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications, 60% M 15 concrete and 40% boulders/stones, using Mechanical Aids	6.51	Cum				
11	Supply & making 60mm to 80mm dia bamboo pile & hamering into the ground including as per size, pointing the end etc complete (no. of pile - 10 no, spacing - 1 m)	234.00	RM				

Shuklaphanta Municipality
Office of Municipal Executive
Jhalaria, Kanchanpur
 Sudurpachin Province, Nepal

BILL OF QUANTITY

प्रमुख प्रशासकीय अधिकारी

Name of Project:- वडाको विभिन्न ठाउँमा तटबन्ध, जैविक तटबन्ध तथा निर्माण कार्य
 Location:- Ward No-02

Municipality:- Shuklaphanta Municipality

FY:2082/83

SN	Description of Items	Quantity	Unit	Rate		Total Amount	Remarks
				Bidder's rate(In Digit)	Bidder's rate(In words)		
12	Supply, Making & Fixing two half pieces from 80mm dia bamboo and fixing them to vertical pole by wire or nail	187.20	SQM				
13	Filling with local sand, sewing them, closed & placing them including hauling up to 100m distance	64.35	CUM				
14	Geo-Textile	362.70	SQM				
Sub-Total Amount							
Vat @ 13 %							
Total Amount							

In words:
 Name of Firm:
 Address of Firm:
 Authorized Signature and Date :
 Office Seal: